Rochester Standard Ranch Specifications

House Floor Width & Roof Standard

Floor width 30', 28', 26' per print, increase length & width optional

Floor crawl space model, basement prep available

Roof truss 6/12 24"oc, (available 9/12), 16"oc available

Roof eave and rake 10"

Roof sheeting 7/16"

Roof sub fascia 2x6

Roof attic access

Ceiling drywall 5/8"

Structural Standards

Floor joist 2x10 16" oc #2 SPF or better

Floor deck 3/4" Tongue & Groove, Ring Shank Nails, Handifoam

Cut back at mate line

Floor band joist doubled sidewall, mate line

Ceiling 8' height throughout (available 9')

Walls exterior 2x6 16" oc, double top plate, ½" drywall Walls interior 2x4 16" oc ½" drywall

Walls mate line 2x3 16" oc ½" drywall

Walls exterior sheeted W/7/16" osb side, end, and mateline

Heating Standards

Heat registers and boots

Main Duct and furnace not provided as std.

Plumbing Standards

1/2" PEX supply lines stubbed through floor per code

Air Hammer Arresters install Washer, DW, if applicable

PVC drain lines stubbed through floor

Shut offs all exposed supply lines

Freeze proof faucet installed, 1 std

Delta single lever faucets, vanity, tubs, kitchen sink-lifetime warranty

Delta gooseneck kitchen faucet sink- lifetime warranty

Stainless steel double bowl sink kitchen

Gerber elongated commode and tank

China lavs with overflows

Fiberglass tub & shower/enclosures, per print

All network of plumbing not included under floor

Electrical Standards

200-amp Siemen service panel 40/40

Copper romex 12-2 wire all general circuits

Copper romex wire other circuits sized accordingly

Ground fault protection per code

Arc fault protection all bedrooms

220V provided for dryer per plan

110V for gas range per plan

Smoke and carbon monoxide detectors per code

3-way switches per plan

Kichler ceiling lights, double bulb, all bedrooms and living room

LED recessed canister lights KIT, Halls, UTL, Master Closet, Per Print

Kichler coach light by all exterior doors

Kichler pendant lights over mirror all baths

Broan light vent combination all baths

Microwave prep standard over future range location

Attic light

Door chime front door

One telephone jack, choose from suggested locations

Exterior GFCI recept front and rear, per code

Tamper resistant recepts

All UTL circuits GFCI, all KIT circuits ARC fault AFCI,

DW GFCI protected

10ft. Thermostat Wire coiled under floor through wall

Furnace prep per print-Finished closet w/ switched light, dedicated switched 110 metal box

W/H prep per print- Finished closet w/ switched light, dedicated 220 metal

Accepted By:	
Date:	

Exterior Finish, Window, Door & Insulation Standards

Tyvek House wrap around entire house, gables included

Ice dam protection eaves

R-21 paperback batt insulation all exterior walls

R38 blown attic insulation

Vinyl 4x4 siding, prepped for sill plate fastening

Vented vinyl soffit

Aluminum fascia

Owens Corning TruDefinition Duration shingles-limited

lifetime warranty

Silverline single hung windows (see Window Options)

Vinyl casement window over kitchen sink- per plan

Grids between glass

Tip out sash Low E2 Argon filled glass with Passive Solar glazing

15" raised panel shutters all windows

Dead bolts keyed alike

Thermatru Fiberglass front door peep hole and knocker 3'0" X 6'8" with

lever action Schlage lockset

Thermatru Steel rear door 20-minute fire rated 2'8" X 6'8" with lever action

Schlage lockset

Caulking under all exterior walls

Cabinet Standards

Merillat Spring Valley Maple stained, recessed panel per plan

30" Overhead wall cabinets

Crown molding over all wall cabinets

Wall cabinets over washer and dryer, per plan

Lazy Susan in corner plan

Raised angle wall cabinet in corner per plan

Raised Pantry Cabinet per plan

Bank of drawers in base cabinets - bathrooms

Laminate counters with rolled edge and Post Form back splash

Interior Door and Trim Standards

White hollow core smooth painted interior doors, choose between 3 styles, 32" where applicable

Colonial style wood base and door casing painted white finish

Mortised hinges all doors

Lever action passage and privacy locksets

Colonial style wood casing and jamb painted white finish all windows

2 1/4" mirror trim stained to match door/window trim color

All interior decorative wood components added will match trim color

Floor Covering Standards

FHA certified wear dated Anso nylon carpet 42 oz. ship loose not installed 5 lb rebond carpet pad ship loose

Vinyl roll goods installed in kitchen, baths, utility, and fover per plan

Interior Finish Standards

Smooth wall finish painted white with hi-build primer

Stipple finish ceiling painted white with hi-build primer

Flush transition at ceiling line no beam

Epoxy coated wire shelves closets

Closet organizer system in Bedroom 1 walk in closet, per print

Appliances

Microwave prep over stove area

No appliances standard

Warranty

One year, 10 year structural as described on web page www.rochesterhomesinc.com (ID102006)



U: Lit Room/Standards Rev. 11/15/2022